

Residential Development, Fortfield Road, Terenure

Existing Pedestrian Bridge Inspection and Assessment Report 222102-PUNCH-XX-XX-RP-C-0010

November 2024



Document Control

Document Number: 222102-PUNCH-XX-XX-RP-C-0010

Status	Rev	Description	Date	Prepared	Checked	Approved
A0	C01	Stage 2 LRD Submission	07/03/2024	JP. Murray	MC. Daly	P. Casey
A0	C02	Stage 2 LRD Submission	11/03/2024	JP. Murray	MC. Daly	P. Casey
A0	C03	Stage 3 LRD Submission	01/11/2024	JP. Murray	MC. Daly	P. Casey





Existing Pedestrian Bridge Inspection and Assessment Report

Table of Contents

Document Control i
Table of Contentsii
1 Introduction1
2 Bridge Description1
3 Visual Inspections (16/05/2022 and 22/02/2024)2
3.1 Bridge Surface2
3.2 Footways/Median2
3.3 Parapet
3.4 Spandrel Walls
3.5 Abutments
3.6 Piers
3.7 Arch Barrels
3.8 Structure in General7
4 Load Capacity Assessment
4.1 Assessment of Typical Masonry Arch (Modified MEXE Method)8
4.1.1 Span 1
4.1.2 Span 2 10
4.1.3 Span 3 12
4.2 Assessment of pedestrian and cyclist load capacity
5 Conclusions 15
Appendix A Site Inspection Photographs (16/05/2022)A-I
Appendix B Modified MEXE Methd AnalysisB-I
Appendix C Site Inspection Photographs (22/02/2024)C-I



1 Introduction

PUNCH Consulting Engineers undertook a structural inspection and load capacity assessment of the existing 3-span masonry arch bridge located on the eastern extents of the site's lake walk. The purpose of the bridge inspection/assessment is to determine its load carrying capacity in order to demonstrate its ability to function for the intended pedestrian and cyclist loading.



Figure 1: Location Map.

2 Bridge Description

The bridge is a 3 no. masonry arch pedestrian bridge over the local watercourse. The bridge spans consists of irregular arches, varying between round and segmental and of varying spans and heights.

The bridge structure consists of rubble limestone walls with render finish and rubble limestone parapet walls with angled masonry cappings.



3 Visual Inspections (16/05/2022 and 22/02/2024)

A visual walkover survey of the bridge was undertaken on Monday 16th 2022 by Stephen Maher and Karl Mullins (PUNCH Consulting Engineers). This bridge inspection incorporated field measurements and visual inspection only. No material testing was undertaken on the bridge given the status of the on-going initial capacity assessment.

A follow-up visual walkover survey of the bridge was conducted on Thursday 22nd February 2024 to assess any potential changes in the interim period. No appreciable changes to the bridge condition was observed.

The inspections of the bridge was undertaken in line with standards BD 21/14 (Volume 3, Section 4, Part 1 'The Assessment of Road Bridges and Structures') and TII Publication AM-STR-06002 (Volume 3, Section 4, Part 2 'The Assessment of Road Bridges and Structures'). Sufficient detailed information was derived from the survey to allow subsequent assessment of the masonry arches by the modified MEXE method, should it be required by Council at a later stage. The required dimensional details and factors affecting the various modifying factors (e.g. material type used for the arch barrel, type of construction of the barrel, width of mortar joints, etc.) have been determined.

The results of the detailed structural inspection are described in terms of key bridge components similar to the standard Eirspan template.

3.1 Bridge Surface

The bridge surface is in poor condition. The wearing course is deteriorating or non-existent in places with the arch barrel exposed in places, representing a tripping hazard. It is recommended that replacement of the bridge surfacing is undertaken in accordance with the landscape architectural recommendations, with the provision of a 100mm thick wearing surface build-up throughout the bridge extents.



Figure 2 - Bridge Surface

3.2 Footways/Median

The masonry arch structure serves to carry a narrow (1.2m wide between parapets) pedestrian pathway over the local watercourse at this location.





Figure 3 - Narrow Width of Bridge

3.3 Parapet

The parapet wall is typically in the order of 400mm high relative to the existing bridge surface. The introduction of 100mm depth of new surfacing will further reduce the height of the parapet to 300mm relative to the walking surface.

Iron posts are cast into the parapet at regular 3m intervals. It is presumed that a chain previously ran between these posts to offer additional restraint to pedestrians.

The parapet wall is in reasonably good condition. Some localised masonry loss and damage observed to coping.



Figure 4 - Short Parapet Height





Figure 5 - Historic Iron Posts



3.4 Spandrel Walls

The western spandrel walls appear in good condition with no significant cracking or bulging observed on this upstream bridge elevation.



Figure 6 - Western/Upstream Spandrel Wall

The eastern spandrel walls appear in good condition generally with no significant cracking or bulging observed on this elevation for the Spans 2 and 3 extents. However, there is a significant diagonal crack observed over the Span 1 arch. This longitudinal crack has been previously patched with mortar, obscuring the width and depth of the cracking in the previous mortar joints.



Figure 7 - Eastern/Downstream Spandrel Wall





Figure 8 - Crack in Parapet and Spandrel Wall over Span 1 (Eastern Elevation)

3.5 Abutments

The abutments are in good condition generally, but some mortar loss was observed in the abutment masonry.

3.6 Piers

The piers are in good condition generally, but some mortar loss was observed in the masonry throughout.

3.7 Arch Barrels

The arch barrels do not exhibit any significant transverse or longitudinal cracking with the exception of a longitudinal crack in Span 2 coinciding with the western parapet. There is widespread mortar loss throughout the arch barrels. The joints between barrel stones are insufficiently filled to depths in the range of 10-20mm. The remaining mortar is generally loose and friable.



Figure 9 - Span 2 Arch Barrel





Figure 10 - Span 2 Arch Barrel

3.8 Structure in General

The structure is generally in good condition. The principal defects associated with the bridge are as follows:

- 1) Inadequate depth of fill/surface cover over masonry barrel arches.
- 2) Inadequate height of parapet/restraint system for pedestrians and cyclists.
- 3) Longitudinal crack in Span 2 coincident with western parapet/spandrel wall.
- 4) Longitudinal crack in parapet/spandrel wall above Span 1 on eastern bridge elevation.
- 5) Some loss of mortar throughout the barrel arches.

The defects do not represent a concern for the on-going function of the pedestrian bridge. However, remedial works to improve the bridge should be considered in light of proposals to improve the lakeside walks as part of the proposed Fortfield Road LRD proposals.



4 Load Capacity Assessment

4.1 Assessment of Typical Masonry Arch (Modified MEXE Method)

Following completion of the structural inspection, an assessment of the strength of the arch barrels was undertaken for the bridge using the Modified MEXE Method outlined in TII Publication AM-STR-06002 '*The Assessment of Road Bridges and Structures*' Section 3. The assessment was based on recorded measurements, observed type and condition of materials and joints.

4.1.1 Span 1

Recorded Geometry for Span 1:

(Span)
(Rise of the arch barrel at the crown)
(Rise of the arch barrel at the quarter point)
(Thickness of the arch barrel adjacent to the keystone)
(Average depth of fill)

The provisional axle loading (PAL) is obtained by reference to expression below derived from Figure 3.1 of AM-STR-06002 below.

$$PAL = \frac{740(d+h)^2}{L^{1.3}}$$

- PAL = 62 Tonnes
- F_{sr} = 1.0 (AM-STR-06002, Figure 3.3)
- F_p = 0.81 (AM-STR-06002, Figure 3.4)
- $F_m = 0.91$ (assuming $F_b = 1.0$ and $F_f = 0.7$. AM-STR-06002 Tables 3.1 & 3.2)
- $F_j = 0.58$ (assuming $F_w = 0.8$, $F_d = 0.8$ and $F_{mo} = 0.9$. AM-STR-06002 Tables 3.3-3.5)
- F_{cm} = 0.6 (based on observed cracking at arch barrel)

• Modified Axle Load = $F_{sr} \cdot F_{p} \cdot F_{m} \cdot F_{j} \cdot F_{cm} \cdot PAL$

= 15.75 Tonnes

- Axle Factors (No Axle Lift-Off) from AM-STR-06002 Figure 3.5a:
 - Single Axle = 1.0
 - 2 Axle Bogey = 1.0
 - 3 Axle Bogey = 1.0
- Allowable Axle Loads (No Axle Lift-Off):
 - Single Axle = 16 Tonnes (refer to AM-STR-06002 Section 3.30)
 - 2 Axle Bogey = 16 Tonnes (refer to AM-STR-06002 Section 3.30)
 - 3 Axle Bogey = 16 Tonnes (refer to AM-STR-06002 Section 3.30)

Taking these Allowable Axle Loads, the capacity of the arch is determined in terms of gross weights from Table 3.6 of AM-STR-06002 below.



Allowable Axle Load (tonnes) per axle		Max Gross	Weight	Туре	
Single	Double	Triple	(gvw) (tonnes)	(tonnes)	oi Vehicle
11.5	10	8*	40/44	N/A	HGV-5 or 6 axles
11.5	9.5	-	32	33	HGV-4 axles
11.5	9.5	-	26	26	HGV-3 axles
11.5	-	-	18	18	HGV-2 axles
9	-	-	12.5	13	
7	-	-	10	10	
5.5	-	-	7.5	7.5	LGV
2	-	-	3	3	Car/Van

In the case of this bridge span, the Max Gross Vehicle Weight (gvw) is 40/44 Tonnes.

Therefore, weight restrictions are not applicable to this particular arch only.



4.1.2 Span 2

Recorded Geometry for Span 2:

L = 1.96m	(Span)
r _c = 0.91m	(Rise of the arch barrel at the crown)
r _q = 0.78m	(Rise of the arch barrel at the quarter point)
d = 0.24m	(Thickness of the arch barrel adjacent to the keystone)
h = 0.10m	(Average depth of fill)

The provisional axle loading (PAL) is obtained by reference to expression below derived from Figure 3.1 of AM-STR-06002 below.

$$PAL = \frac{740(d+h)^2}{L^{1.3}}$$

- PAL = 36 Tonnes
- F_{sr} = 1.0 (AM-STR-06002, Figure 3.3)
- F_p = 0.72 (AM-STR-06002, Figure 3.4)
- $F_m = 0.91$ (assuming $F_b = 1.0$ and $F_f = 0.7$. AM-STR-06002 Tables 3.1 & 3.2)
- $F_j = 0.58$ (assuming $F_w = 0.8$, $F_d = 0.8$ and $F_{mo} = 0.9$. AM-STR-06002 Tables 3.3-3.5)
- F_{cm} = 0.70 (based on observed cracking at arch barrel)
- Modified Axle Load = $F_{sr} \cdot F_{p} \cdot F_{m} \cdot F_{j} \cdot F_{cm} \cdot PAL$

= 9.38 Tonnes

- Axle Factors (No Axle Lift-Off) from AM-STR-06002 Figure 3.5a:
 - Single Axle = 1.0
 - 2 Axle Bogey = 1.0
 - 3 Axle Bogey = 1.0
- Allowable Axle Loads (No Axle Lift-Off):
 - Single Axle = 9 Tonnes (refer to AM-STR-06002 Section 3.30)
 - 2 Axle Bogey = 9 Tonnes (refer to AM-STR-06002 Section 3.30)
 - 3 Axle Bogey = 9 Tonnes (refer to AM-STR-06002 Section 3.30)

Taking these Allowable Axle Loads, the capacity of the arch is determined in terms of gross weights from Table 3.6 of AM-STR-06002 below.

Allowable Axle Load (tonnes) per axle		Max Gross	Weight	Туре	
Single	Double	Triple	(gvw) (tonnes)	(tonnes)	ol Vehicle
11.5	10	8*	40/44	N/A	HGV-5 or 6 axles
11.5	9.5	-	32	33	HGV-4 axles
11.5	9.5	-	26	26	HGV-3 axles
11.5	-	-	18	18	HGV-2 axles
9	-	-	12.5	13	
7	-	-	10	10	
5.5	-	-	7.5	7.5	LGV
2	-	-	3	3	Car/Van



In the case of this bridge span, the Max Gross Vehicle Weight (gvw) is **12.5 Tonnes**.

According to the Modified MEXE Method analysis, this will necessitate a <u>Weight Restriction of 13 tonnes</u> (HGV - 2 axles) on this particular arch and therefore the bridge in its entirety.



4.1.3 Span 3

Recorded Geometry for Span 3:

L = 1.28m	(Span)
r _c = 0.31m	(Rise of the arch barrel at the crown)
r _q = 0.38m	(Rise of the arch barrel at the quarter point)
d = 0.24m	(Thickness of the arch barrel adjacent to the keystone)
h = 0.10m	(Average depth of fill)

The provisional axle loading (PAL) is obtained by reference to expression below derived from Figure 3.1 of AM-STR-06002 below.

$$PAL = \frac{740(d+h)^2}{L^{1.3}}$$

- PAL = 62 Tonnes
- F_{sr} = 1.0 (AM-STR-06002, Figure 3.3)
- F_p = 0.81 (AM-STR-06002, Figure 3.4)
- $F_m = 0.91$ (assuming $F_b = 1.0$ and $F_f = 0.7$. AM-STR-06002 Tables 3.1 & 3.2)
- $F_i = 0.58$ (assuming $F_w = 0.8$, $F_d = 0.8$ and $F_{mo} = 0.9$. AM-STR-06002 Tables 3.3-3.5)
- F_{cm} = 0.75 (based on observed condition of arch)
- Modified Axle Load = $F_{sr} \cdot F_{p} \cdot F_{m} \cdot F_{j} \cdot F_{cm} \cdot PAL$

= 19.68 Tonnes

- Axle Factors (No Axle Lift-Off) from AM-STR-06002 Figure 3.5a:
 - Single Axle = 1.0
 - 2 Axle Bogey = 1.0
 - \circ 3 Axle Bogey = 1.0
- Allowable Axle Loads (No Axle Lift-Off):
 - Single Axle = 20 Tonnes (refer to AM-STR-06002 Section 3.30)
 - 2 Axle Bogey = 20 Tonnes (refer to AM-STR-06002 Section 3.30)
 - 3 Axle Bogey = 20 Tonnes (refer to AM-STR-06002 Section 3.30)

Taking these Allowable Axle Loads, the capacity of the arch is determined in terms of gross weights from Table 3.6 of AM-STR-06002 below.



Allowable Axle Load (tonnes) per axle		Max Gross	Weight	Туре	
Single	Double	Triple	(gvw) (tonnes)	(tonnes)	ol Vehicle
11.5	10	8*	40/44	N/A	HGV-5 or 6 axles
11.5	9.5	-	32	33	HGV-4 axles
11.5	9.5	-	26	26	HGV-3 axles
11.5	-	-	18	18	HGV-2 axles
9	-	-	12.5	13	
7	-	-	10	10	
5.5	-	-	7.5	7.5	LGV
2	-	-	3	3	Car/Van

In the case of this bridge span, the Max Gross Vehicle Weight (gvw) is $\underline{40/44 \text{ Tonnes}}$.

Therefore, weight restrictions are not applicable to this particular arch only.

Refer to Appendix B for all of Modified MEXE Method calculation spreadsheets.

SpanMax Gross Vehicle
Weight (gvw)Restrictions140/44 TonnesNone212.5 tonnesHGV - 2 axles only with
Weight Restriction = 13 tonnes340/44 TonnesNone

The summary of the Modified MEXE Method analyses is provided below:

Span 2 presents the limiting capacity of the bridge and the magnitude and effects of the associated limiting vehicle are then compared to the magnitude and effects of pedestrian and cyclist load case.

4.2 Assessment of pedestrian and cyclist load capacity

The effect of the 12.5 tonnes gross vehicle weight 2 axle HGV can be assessed using the Service Vehicle load model as presented in clause 5.3.2.3 of I.S. EN 1991-2+NA:2009 Eurocode 1: Actions on structures - Part 2: Traffic loads on bridges (Including Irish National Annex). The graphical representation of this Service Vehicle is included below, it is noted the 120 kN of force represents 12.2 tonnes of mass which is closely comparable to the 12.5 tonnes limiting HGV of Span 2.







The referred Eurocode in clause 5.3.2.1 also specifies pedestrian and cyclist loading which equates to $5kN/m^2$. The deck contributary area of span two can be conservatively approximated as $(1.5m)(2m) = 3m^2$, resulting in design value of 15kN of force transferred to the arch. As this is considerably less than the magnitude of force transferred to the arch from even a single wheel of the Service Vehicle, it is concluded that required capacity to accommodate pedestrian and cyclist loading is less than required capacity to accommodate pedestrian and cyclist loading is less than the bridge in its entirety has sufficient capacity to accommodate pedestrian and cyclist loading.



5 Conclusions

- 1) The masonry arch bridge is generally in good condition. However a number of defects are noted:
 - i. Inadequate depth of fill/surface cover over masonry barrel arches.
 - ii. Inadequate height of parapet/restraint system for pedestrians and cyclists.
 - iii. Longitudinal crack in Span 2 coincident with western parapet/spandrel wall.
 - iv. Longitudinal crack in parapet/spandrel wall above Span 1 on eastern bridge elevation.
 - v. Some loss of mortar throughout the barrel arches.
- 2) Following a structural analysis of the bridge structure, it is concluded that the bridge (in its existing condition) has sufficient load carrying capacity to accommodate the pedestrian/cyclist traffic.
- 3) Repointing is recommended throughout the bridge at multiple locations, particularly to the arch barrels on all three spans. The loss of mortar throughout the arch barrels leads to a loss of strength to the bridge arches in the analyses. The loss of mortar also accelerates the deterioration of the arch over time, increasing the risk of arch separation and stone displacement in the barrel. A lime-based mortar is recommended.
- 4) Provision of a 100mm thick wearing surface build-up throughout the bridge extents is recommended. This should be specified in consultation with landscape architectural recommendations.
- 5) An assessment of pedestrian safety in the context of low height parapet walls is recommended. This would benefit from consultations with a conservation architect.
- 6) Detailed record photographs of the bridge should be taken in advance of any remedial works for record purposes.
- 7) It is recommended that periodic inspections of the bridge are undertaken to monitor for any signs of distress or deterioration of the bridge.



Appendix A Site Inspection Photographs (16/05/2022)





Site Photo 1







Site Photo 3







Site Photo 5







Site Photo 7







Site Photo 9







Site Photo 11







Site Photo 13







Site Photo 15







Site Photo 17







Site Photo 19







Site Photo 21







Site Photo 23





Residential Development, Fortfield Road, Terenure

Existing Pedestrian Bridge Inspection and Assessment Report



Site Photo 25







Site Photo 27







Site Photo 29





Appendix B Modified MEXE Methd Analysis

		Fortfield Road - Pedestrian Bridge - Span 1			Job No: 222102	
	UNCH	Assess	ment using BA1	6/14 MEXE Method	Sheet No: 1	Rev: RO
cons	consulting engineers		Pedestrian Bridge Calc by: DW		Check by:	Date:
		redestrian bruge		Date: 17-05-2022	KOR	18/05/2022
Ref		Calo	ulations		Οι	utput
BA 16/14	Modified MEXE Method	k				
3.5	Arch Dimensions					
	Span	L (m)			1.28	
	Rise at Crown	r _c (m)			0.46	
	Rise at Quarter Point	r _a (m)			0.38	
	Ring Thickness	d (m)			0.24	
	Depth of Fill	h (m)			0.10	
		. ,				
3.10	Provisional Assessment					
	Provisional Axle Loading	; (P.A.L.)				
	From Fig. 3/1 Nonogram	n, or <u>740 x</u>	<u>‹ (d+h)²</u> , or ʾ L ^{1.3}	70	62.06	
	Modifying Factors					
3.11	Span/Rise Factor	F _{sr}	Fig. 3.3	3	1.00	
		L/r _c			2.78	
3.12	Profile Factor	Fp	= 2.3 x [(r _c - r _a)/r _c] ^{0.6}	0.81	
3.13	Material Factor	Fm	= <u>(F_b x d</u>) + (F _f x h)	0.91	
				h + d		
3.16	Joint Factor	F_{j}	$= F_w \times F_n$	_{no} x F _d	0.58	
3.17	Condition Factor	F _{cM}			0.60	
Table 3.1	Barrel Factor	F _b			1.00	
Table 3.2	Fill Factor	F _f			0.70	
Table 3.3	Joint Width Factor	Fw			0.80	
Table 3.4	Joint Mortar Factor	F _{mo}			0.90	
Table 3.5	Depth factor	F _d (m)			0.80	
Annex G						_
	Horizontal Curve Radius	<i>,</i> r (m)			> 600	
	v2 = <u>1000r</u>	Centrif	ugal Effect Facto	r F _A = 1 + (0.2v ² /r) =	N/A	
	r + 150					
2.24	Madified Auto Load				15 75	
3.24			IVI.A.L. = $F_{sr} \times F_{p}$	X F _m X F _j X F _{cM} X P.A.L	15.75	
	For Z-Axie Bogie (IVI.A.L)					
3.27	Axle Lift Off (Y/N)	N/A				
	Axle Factor	A _f see F	ig. 3/5a & 3/5b			
	Singe Axle	1.00 Allow	vable A.L.		16	
	2 Avia Dagia	1.00 Allo			16	
	Z-AXIE BOgie	1.00 Allov	vaule A.L.		10	
	3-Axle Bogie	1.00 Allow	vable A.L.		16	
Table 3/6	LOAD CAPACITY	Max	G.V.W. (tonne	es)	40/44	
			(,	

		Fortfield Road - Pedestrian Bridge - Span 2			Job No: 222102		
P	UNCH	Asse	ssment using	BA16/14 M	MEXE Method	Sheet No: 1	Rev: RO
cons	consulting engineers		lestrian Bridø	۵	Calc by: DW	Check by:	Date:
	1		redestrian bruge		Date: 17/05/2022	KOR	18/05/2022
Ref		C	alculations			Οι	utput
BA 16/14	Modified MEXE Method	d					
3.5	Arch Dimensions						
	Span	L (m)			1.96	
	Rise at Crown	r _c (m)			0.91	
	Rise at Quarter Point	r _a (m)			0.78	
	Ring Thickness	d (m)			0.24	
	Depth of Fill	h (m)			0.10	
2 10	Provisional Assessment						
5.10	Provisional Ayle Loading	- (ΡΔΙ)					
	From Fig. 3/1 Nonogram	or 74	$0 \times (d+h)^2$	or 70		35.67	
	i tom ng. 3/ i Nonogran	, or <u>, ,</u>	L ^{1.3}	0170		55.07	
	Modifying Factors						
3.11	Span/Rise Factor	F _{sr}	Fi	g. 3.3		1.00	
		L/r _c				2.15	
3.12	Profile Factor	F _p	= 2	.3 x [(r _c - r _a)/r _c] ^{0.6}	0.72	
3.13	Material Factor	Fm	= <u>(</u> F	F _b x d) + (F _f	<u>x h)</u>	0.91	
				h + d			
3.16	Joint Factor	F _i	= F,	w x F _{mo} x F _d	l	0.58	
3.17	Condition Factor	F _{cM}				0.70	
Table 3.1	Barrel Factor	F _b				1.00	
Table 3.2	Fill Factor	F _f				0.70	
Table 3.3	Joint Width Factor	Fw				0.80	
Table 3.4	Joint Mortar Factor	F_{mo}				0.90	
Table 3.5	Depth factor	F _d (m)			0.80	
Annex G							
	Horizontal Curve Radius	s, r (m)				> 600	
	v2 = <u>1000r</u>	Centr	ifugal Effect F	actor $F_A =$	1 + (0.2v ² /r) =	N/A	
	r + 150						
						0.00	
3.24	For 2 Avia Dagia (MAAL)		$WI.A.L. = F_{g}$	_{sr} X F _p X F _m :	х ғ _ј х ғ _{сМ} х Р.А.L	9.38	
	For 2-Axie Bogie (IVI.A.L))					
3.27	Axle Lift Off (Y/N)	N/A					
	Axle Factor	A _f se	e Fig. 3/5a & 3	3/5b			
	Singe Axle	1.00 All	owable A.L.			9	
	2-Axle Bogie	1.00 All	owable A.L.			9	
	3-Axle Bogie	1.00 All	owable A.L.			9	
				-		_	
Table 3/6	LOAD CAPACITY	M	ax G.V.W. (t	onnes)		12.5	

		Fortfield Road - Pedestrian Bridge - Span 3				Job No: 222102		
	UNCH	Assessm	Assessment using BA16/14 MEXE Method			Rev: RO		
cons	sulting engineers	Padastr	Calc by: DW		Check by:	Date:		
		redesthan bruge		Date: 17-05-2022	KOR	18/05/2022		
Ref		Calcul	ations		0	utput		
BA 16/14	Modified MEXE Method	ł						
3.5	Arch Dimensions							
	Span	L (m)			1.28			
	Rise at Crown	r _c (m)			0.46			
	Rise at Quarter Point	r _q (m)			0.38			
	Ring Thickness	d (m)			0.24			
	Depth of Fill	h (m)			0.10			
3.10	Provisional Assessment							
	Provisional Axle Loading	; (P.A.L.)						
	From Fig. 3/1 Nonogram	n, or <u>740 x (</u>	<u>d+h)², or 7(</u> ^{1.3})	62.06			
	Modifying Factors							
3.11	Span/Rise Factor	F _{sr}	Fig. 3.3		1.00			
		L/r _c			2.78			
3.12	Profile Factor	Fp	= 2.3 x [(r	_c - r _a)/r _c] ^{0.6}	0.81			
3.13	Material Factor	F _m	= <u>(F_b x d)</u>	+ (F _f x h)	0.91			
			h	+ d				
3.16	Joint Factor	Fj	$= F_w \times F_{mo}$	x F _d	0.58			
3.17	Condition Factor	F _{cM}			0.75			
Table 3.1	Barrel Factor	F _b			1.00			
Table 3.2	Fill Factor	F _f			0.70			
Table 3.3	Joint Width Factor	Fw			0.80			
Table 3.4	Joint Mortar Factor	F _{mo}			0.90			
Table 3.5	Depth factor	F _d (m)			0.80			
Annex G								
	Horizontal Curve Radius	<i>,</i> r (m)		24	> 600			
	v2 = <u>1000r</u>	Centrifug	al Effect Factor	F _A = 1 + (0.2v ² /r) =	N/A			
	r + 150							
3.24	Modified Axle Load	Μ	.A.L. = E., x E. x	K Fm x Fi x Fm x P.A.L	19.68			
•	For 2-Axle Bogie (M.A.L)		21 h					
3.27	Axle Lift Off (Y/N)	N/A						
	Axle Factor	A _f see Fig	. 3/5a & 3/5b					
	Singe Axle	1.00 Allowa	ble A.L.		20			
	2-Axle Bogie	1.00 Allowa	ble A.L.		20			
	3-Axle Bogie	1.00 Allowa	ble A.L.		20			
Table 3/6	LOAD CAPACITY	Max G	.V.W. (tonnes)	40/44			



Appendix C Site Inspection Photographs (22/02/2024)





Site Photo 31



Site Photo 32





Site Photo 33



Site Photo 34